


MONTANA HISTORICAL AND ARCHITECTURAL
INVENTORY FORM



Roll# 11 Frame# 15

Legal Description: Pepin's Second Addition, Block 9, Part of Lot 7 and All of Lot 8

Address: 629 Sixth Avenue

Ownership Name: David L. Deschliman

Address: 629 Sixth Avenue, Havre, MT 59501

private: x

public:

Historic Name: Christ Fuglevand House

Common Name: Christ Fuglevand House

Date of Construction: 1929 (water record)

Architect: N/A

Builder: probably Christ Fuglevand

Original Owner: Christ Fuglevand

Original Use: Single-family residence

Present Use: Single-family residence

Physical Description:

One-and-one-half story, 3 x 3 bay, wood-frame single-family Cottage style residence. Gable roof with no eaves and ridgeline parallel to street. Wood-shingled roof. Stucco exterior. Raised concrete foundation.


Main central entry is contained within foyer that in turn is concealed within a large false exterior chimney. The false chimney is pierced with side windows that are 6/1 double-hung

with wood sash and sill. A wooden shield with a coat of arms is applied to the exterior directly above the main entry. Entry access is via a small flight of concrete stairs flanked by concrete sidewalls and decorative metal scrollwork.

The main (W) facade also includes two large c. 1970 picture windows that flank the main entry. Side (N & S) gable windows are 6/1 double hung with wood sash and sill and are doubled. The daylight basement features 3-light wood casement windows.


The site is raised well above the street and requires a concrete retaining wall along the west edge of the property before meeting the sidewalk.

Associated structures:



Roll #29 Frame #13A

1) C. 1929 large wood-framed shiplap-sided carpentry shop. Wood-shingled gable roof with open eaves and exposed rafters. Faces east with access via the rear service alley. Large pair of sliding wood doors cover main centrally-located entry bay. Main (E) gable has access to loft area. the building retains its architectural integrity and historic character and should considered a contributing structure within the proposed historic district. The original building permit indicates that the building was constructed in 1929 for a total estimated cost of \$600.00 by Christ Fuglevand for himself.



Roll # 29 Frame #12A

2) Single-bay, wood-frame garage. Faces east with access via rear service alley. Wood-shingled hip roof. C. 1970 vertical board siding. The building permit for the garage is dated 1935 and shows that it was built for a total estimated cost of \$100.00 by Christ Fuglevand. This building retains its original configuration and some of its historic fabric. The new siding might be reversible. This building, then should be considered as a contributing element within the proposed historic district.

Historical Information:

According to the original building permit, dated 1929, this building was constructed by Christ Fuglevand for himself for a total estimated cost of \$4000.00. In an article appearing in the Daily News in September, 1929, the foundation for the residence had just been poured and Fuglevand was ready to begin construction of the stucco over wood frame building. Christ Fuglevand was probably Havre's most prominent and prolific builder-contractor and was most likely built by Christ Fuglevand (SEE Christ Fuglevand - Historic Overview).

Footnote Sources:

1. Havre Daily News, September 24, 1929.

Building Permit Nos. 1235, 1359, 1580, Dated March 4, 1929, September 10, 1929, July 17, 1935, respectively, Department of Public Works, City of Havre, Havre, Montana.

Polk's Directory, Havre and Hill County, 1929-30.

Sanborn Maps: 1920, 1939.

Research Sources:

Assessor's Records, Hill County, Hill County Courthouse, Havre, Montana.

Water Record no. 1251 (1929) and Sewer Record no. 1026 (1929), Department of Public Works, City of Havre, Havre, Montana.

Integrity:

The integrity of the main house has been diminished by the alterations of the windows on the main facade. It does however retain its original configuration, most of its historic fabric (exterior stucco walls) and several stylistic features and details (unusual false chimney).

Significance:

This structure was built by a locally prominent builder and business. Its use of a decorative coat of arms made of wood and applied to a prominent position on the main facade is indicative of this builder. The use of a large false element (i.e. chimney) is unusual. This building would qualify for the National Register under criteria C as a contributing element within the proposed historic district.

Form Prepared By:

Name: Richard Bernstein

Address: Bear Paw Development Corp., PO Box 1549, Havre, MT 59501

Date: March 9, 1988

Revisions: June 22 and October 14, 1988

Geographical Information:

Acreage: Less than one acre

USGS Quad: Havre, Montana

UTM's: